

West Bengal State Agricultural Marketing Board



“Kamal Guha Krishi Bipanan Bhawan”,
729, Anandapur, P.O. E.K.T.P., P.S. Anandapur, Kolkata – 700 107
Mail Id:- wbstatemarketing@yahoo.co.in

NOTICE INVITING QUOTATION

Memo No. : 2880/EC/Gen/42/2022-23

Date: 21/11/2022

Sealed Quotations in letterhead are invited from the interested firms for the following item of works (Copy enclosed). The last date for submission of quotation is **14.00 Hrs. of 25/11/2022**, which will be accompanied by self attested PAN Card, GST and Trade License,

Enclo : List of Items of works.


Terms and Conditions

1. The Chief Executive Officer, West Bengal State Agricultural Marketing Board reserves the right :
 - i) to cancel or reject any bid and ii) to cancel the Quotation process at any stage without assigning any reason thereof.
2. The Rate to be quoted including of all taxes and charges.

A handwritten signature in blue ink, appearing to be 'D. Das', is written over a diagonal line.

Chief Executive Officer
West Bengal State Agricultural Marketing Board

SL.NO.	ITEM DETAIL	Qty	Unit	Unit Rate	Amount
	Reorientation of Agriculture Marketing Dept :- Principal Secretary Room				
1	New Full Height 150mm Thk. Wooden Partition with Solid Wood Frame 2200mm height with 12mm Ply fixed on Both Sides and Finished with Veneer. CNC Jali Design for 600 mm Fixed at Top Part of The Partition. (b) Ordinary teak.	130	Sq.Ft.		
2	Demolition & Dismantling of Existing Full Height Partintion. (330 sqft)	2	Pcs		
3	Full Height 75mm Wooden Partition with Solid Wood Frame,Partly reutilizing the old wooden partition wall comprising of wooden structure and particle bioard with veneered finished and partly mew one with same materials excluding finishing. (b) Ordinary teak.	102	Sq.Ft.		
	2600 mm Height x3650 mm Length x 150mm Breadth				
4	New Full Height Wooden Wall Paneling with Solid Wood Frame with 12mm Ply fixed on Exposed Side and Finished with Veneer. (b) Ordinary teak.	120	Sq.Ft.		
5	Veneer Polish Work of New Full Height Wooden Wall Panel	640	Sq.Ft.		
6	Shifting & Fitting , Fixing Existing Flush Door at Principal secretary Room	1	Nos.		
9	Venisine Blends for windows fitted at Principal Sir's ante Chamber with Steel Rod .	56	Sq.Ft.		
10	Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system at regular interval of 600 mm to form a modular grid of a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 4 mm thick High Pressure Steam Cured Non Asbestos Fibre Cement Standard Ceiling Board Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-in-charge.2' x 2' Gride False Celling for Principle Secretary Sir's Room.	117	Sq.Ft.		
11	Veneer Polish Work for Storage cabinet at Principal secretary Room	20	Sq.Ft.		


 16.11.22
 Sub-Asst. Engineer (Civil)
 W.B.S.A.M.B.

SL.NO.	ITEM DETAIL	Qty	Unit	Unit Rate	Amount
	Reorientation of Agriculture Marketing Dept : - Visitor's Waiting Area.				
15	ACP Paneling Work to Block Upper Part of Existing Aluminium Partition	54	Sq.Ft.		
	Reorientation of Agriculture Marketing Dept : - Principal Secretary P.A Room				
	Pantry Area				
18	Shifting & Re-installing of Existing Full Height Aluminium Partition Complete with Partly Glass & ACP Paneling.	1	Pcs		
19	New Aluminium Glass Door Fitting (3'x7')	1	No.		
20	12 Ft. Long Pantry Counter Storage Cabinet with 12 mm Water Proofing ply Top & Steel Sink fitted above Granite at corner ,Cabinet made of Ply with Laminate finish with Proper locking arrangement with modern fittings etc as per direction of Engineer in Charge. Polish finish inside Size:- 3000x600x800(H) and Granite slab of size 600x600x20	1	Set		
21	Plumbing Work for suppling ,fitting ,fixing Chromium plated Bib Cock (angular shape with wall flange) and Chromium plated Stop Cock fitted with PVC pipes of approved make of (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads,fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps with labour.	1	Ls		


 18/11/22
 Sub-Asst. Engineer (Civil)
 W.B.S.A.M.B.

	Reorientation of Agriculture Marketing Dept : - Special Secretary's Room				
24	Partition of commercial ply as per design fitted and fixed complete including the supporting framework and labour charges for new Full Height 75mm Wooden Partition with Solid Wood Frame with 12mm Ply fixed on Both Sides and Finished with Veneer of 12' in length and 10' wide. (b) Ordinary teak.	120	Sq.Ft.		
25	Supplying solid flush type doors of commercial quality, the timber frame consisting of top and bottom rails and side styles of well seasoned timber 65mm wide each and the entire frame fitted with 37.5mm wide battens places both ways in order to make the door of solid core and internal lipping with Garjan or similar wood veneers using phenol formaldehyde as glue etc. complete, including fitting, fixing shutters in position but excluding the cost of hinges and other fittings in forth floor for New Flush Door Fitting (3'x7')	1	No.		
	Reorientation of Agriculture Marketing Dept : - Joint Secretary's Room				
27	Partly glazed and partly panelled partition or fixed glazing made of extruded and anodised alloy aluminium sections, fabrications after cutting to proper shape and size, drilling and aligning fitted with inbuilt locking arrangement cutting the glass / board (prelaminated / particle / block) to requisite shape and size moulding the edges fitted and fixed glazing clips and dry set neoprine /EPDM gasket, along with all other necessary arrangements for fixing the partition to walls, floors, beams, columns polysulphide sealant for water proofing if necessary complete in all respect as per drawing and specifications and direction of the Engineer in charge. New 7 Ft. Height Aluminium Partition Complete with Partly Glass & ACP Paneling.	53	Sq.Ft.		


18.11.22

Sub-Asst. Engineer (Civil)
W.B.S.A.M.B.

28	<p>fully glazed single leaf aluminium swing door made of extruded and anodized alloy aluminium sections, fabrication including cutting to proper shape and size, drilling and aligning, fitted with heavy duty hydraulic action floor spring placed in the floor with mending damages, with top pin assembly of approved make and brand, fitted with in built locking arrangement, flush bolt, glazing clips and all other necessary fittings, fixtures, adhesives and joineries, cutting glass of approved make to requisite shape and size fitting with dry set neoprene or EPDM gasketing, cutting to requisite shape and size panel board (prelaminated particle board) fixing them with glazing clips as per drawing, specification and direction of Engineer in charge. New Aluminium Glass Door Fitting (3'x7')</p>	1	Pcs		
31	<p>Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming grooves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP) to Block Upper Part of Existing Civil Wall</p>	30	Sq.Ft.		



 16.11.22
 Sub-Asst. Engineer (Civil)
 W.B.S.A.M.B.

SL.NO.	ITEM DETAIL	Qty	Unit	Unit Rate	Amount
	Reorientation of Agriculture Marketing Dept : - Meeting Room Area				
35	Dismantling carefully wood work in posts, postplates, rafters, partition etc., sorting and stacking servicable materials at site and removing rubbish including labour charges.	1	Pcs		
36	Partition Wall with commercial ply as per design fitted and fixed complete including the supporting framework and labour charges for new Full Height 75mm Wooden Partition with Solid Wood Frame with 12mm Ply fixed on Both Sides and Finished with Veneer of 12' in length and 8' wide.	100	Sq.Ft.		
38	New Veneer Border Pesting on wall of Conference Room of size (5000x300) & (2900 x 300) on both sides	50	Sq.Ft.		
40	Wall Paper on Back Wall Conference Room(5000x2100)	118	Sq.Ft.		
42	French polishing to wood work including preparing surface (ordinary gloss) (a) On new wood work on Veneer Polish Work	7.8	Sq.Ft.		
43	Roller Blinds for all Windows Conference Room	158	Sq.Ft.		


16.11.22

Sub-Asst. Engineer (Civil)
W.B.S.A.M.B.


SL.NO.	ITEM DETAIL	Qty	Unit	Unit Rate	Amount
	Reorientation of Agriculture Marketing Dept : - Assistant Secretary Room Area				
44	Partition Wall with commercial ply as per design fitted and fixed complete including the supporting framework and labour charges for new Full Height 75mm Wooden Partition with Solid Wood Frame with 12mm Ply fixed on Both Sides and Finished with Veneer of 12' in length and 8' wide. New 4 Ft. Height 75mm Wooden Partition with Solid Wood Frame with 12mm Ply fixed on Both Sides and Finished with Veneer.	18	Sq.Ft.		
46	Partition Wall with commercial ply as per design fitted and fixed complete including the supporting framework and labour charges for new Full Height 75mm Wooden Partition with Solid Wood Frame with 12mm Ply fixed on Both Sides and Finished with Veneer of 12' in length and 8' wide. New Full Height Aluminium Partition Complete with Partly Glass & ACP Paneling.	228	Sq.Ft.		
	Reorientation of Agriculture Marketing Dept : - Deputy Director's Room Area				
48	Partly glazed and partly panelled partition or fixed glazing made of extruded and anodised alloy aluminium sections, fabrications after cutting to proper shape and size, drilling and aligning fitted with inbuilt locking arrangement cutting the glass / board (prelaminated / particle / block) to requisite shape and size moulding the edges fitted and fixed glazing clips and dry set neoprine /EPDM gasket, along with all other necessary arrangements for fixing the partition to walls, floors, beams, columns polysulphide sealant for water proofing if necessary complete in all respect as per drawing and specifications and direction of the Engineer in charge. .New Aluminium Glass Door Fitting (3'x7')	2	No.		
49	Shifting of broken wooden & stainless steel chair, table etc. From Khadya Bhavan to Udaynarayanpur K.B. With loading unloading of materials. (Shifting operation done in three phases)	3	Ls		



16.11.2021

Sub-Asst. Engineer (Civil)
W.B.S.A.M.B.

SL.NO.	ITEM DETAIL	Qty	Unit	Unit Rate	Amount
	Reorientation of Agriculture Marketing Dept :- Miscellaneous Work				
50	HMOS VIP Enclosure New Low Height 200mm thk. Wooden partition with Solid Wood Frame with 12mm Ply fixed on Both Sides and Finished with Veneer.	16.1	Sq.Ft.		
52	Sliding Door Solid Wood Frame at Principal Secretary confidential section (3'x7') (b) Ordinary teak.	1	Pc		
53	Door Mat replacing (Green) -Entire Corridor of Agriculture Marketing Dept.	19	Pc		
54	New Door Closer Fittings (Green) -Entire Corridor of Agriculture Marketing Dept. Godrej Hydraulic door closer fitted and fixed complete b) medium type	5	Pc		
55	Repairing of Office Table	12	Pc		
56	Cleaning of Curtains at e- governance Area	1	Ls		
57	Roller Blinds for	140	Sq.Ft.		
	a) Assistant Secretary Room				
	b) Deputy Secretary Room				
	a) Principal Secretary Room				
58	Shifting Work	1	Ls		


 16.11.2022
 Sub-Asst. Engineer (Civil)
 W.B.S.A.M.B.